

総 合 見 積 書

貴社名

担当

物件名

新装工事

お見積総額(税抜き)

¥7,240,000 -

消費税

¥579,200 -

御受渡条件

検収渡しと致します

御取引条件

ご契約書に基づく


見積記載以外の項目は別途費用が掛かります。

御取引期日

ご契約書に基づく

見積有効期限

提出日より30日間



NO	項 目	摘 要	数量	単位	単 価	金 額	備 考
1	解体工事		1	式		86,000	
2	造作木工事・軽鉄軽天工事		1	式		1,910,300	
3	家具工事		1	式		1,200,000	
4	土間・左官工事		1	式		304,500	
5	塗装工事		1	式		675,000	
6	電気設備工事		1	式		423,000	
7	給排水・衛生設備工事		1	式		590,000	
8	給喚気・ダクト設備工事		1	式		303,000	
9	内装工事		1	式		210,000	
10	空調設備工事		1	式			
11	消防設備工事		1	式		250,000	
12	ファサード工事		1	式		645,000	
13	諸経費		1	式		650,000	
14	値引き		1	式		-6,800	
合 計						¥7,240,000	
備 考							

見 積 御 内 記

名称	解体工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	和式トイレ解体	便器・柄	1.0	式		30,000	
2	トイレ入口周り解体	コンクリートブロック・扉	1.0	ヶ所		15,000	
3	発生材処分費		1.0	式		35,000	
4	場内小運搬費		1.0	式		6,000	
				</			

見 積 御 内 訳

名称	造作木工事・軽鉄軽天工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	壁面・間仕切り軽鉄下地		135.0	㎡	3,500	472,500	
2	壁面PB貼り(増し貼り含む)	PB=12.5mm・一部ケイカル貼り	150.0	㎡	1,500	225,000	
3	壁下地入れ	構造用合板12mm	1.0	式		50,000	
4	天井下地組	軽天	30.0	㎡	3,800	114,000	
5	天井PB貼り	PB=12.5mm	30.0	㎡	1,800	54,000	
6	ドア枠造作	柵材T=30mm	35.0	m	4,500	157,500	
7	新設ドア	ラワンランバー30mm 塗装仕上げ用	2.0	枚	42,000	84,000	
8	スイング扉	ラワンランバー24mm 塗装仕上げ用	2.0	式	12,000	24,000	
9	建具取付調整費		1.0	式		80,000	
10	建具金物費		1.0	式		55,000	
11	ファサードラスカット貼り		1.0	式		45,000	
12	ファサード装飾	サンメント	1.0	式		50,000	
13	ガラス取付費	透明ガラス5mm	1.0	式		85,000	
14	同上取付費		2.0	人工	20,000	40,000	
15	雑材・消耗品金物		1.0	式		50,000	
16	置床フローアー	万協束パーチ20mm	30.0	㎡	5,500	165,000	
17	ベニヤ捨て貼り	構造用合板12mm	30.0	㎡	2,000	60,000	
18	天井点検口	450×450	2.0	ヶ所	4,500	9,000	
19	壁点検口	250×250	1.0	ヶ所		3,800	
20	給気口		1.0	ヶ所		6,500	
21	造作黒板	古材枠	1.0	式		80,000	
合 計					1,910,300		

見 積 御 内 記

名称	家具工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	造作テーブル アンティークテーブル	仕様 要打ち合わせ 概算	1.0	台		185,000	
2	造作カウンター	仕様 要打ち合わせ 概算	1.0	台		280,000	
3	レジ台	仕様 要打ち合わせ 概算	1.0	台		125,000	
4	スライサー台	仕様 要打ち合わせ 概算	1.0	台		55,000	
5	陳列棚1000W	IRONブラケット受け	2.0	台	45,000	90,000	
6	陳列棚600W	IRONブラケット受け	1.0	台		35,000	
7	出入口 親子扉(親)	造作框ドア T=35mm	1.0	枚		135,000	
8	出入口 親子扉(子)	造作框ドア T=35mm	1.0	枚		95,000	
9	室内引違い戸	フラッシュドア	2.0	枚	100,000	200,000	
合 計						1,200,000	



見 積 御 内 記

名称	土間・左官工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	発砲ウレタンフォーム・ワイヤーメッシュ敷き	オープン下部のみ 厚100	3.0	m ²	3,500	10,500	
2	土間コンクリート打設	オープン下部のみ 厚100	3.0	m ²	12,500	37,500	
3	販売スペースモルタル打設	厚45	18.0	m ²	7,500	135,000	
4	同上ワイヤーメッシュ床処理		18.0	m ²	1,500	27,000	
5	ファサード壁面 モルタル左官仕上	補修材 金コテ押え	4.0	m ²	6,500	26,000	
6	ファサードタイル貼り	サブウェイタイル	3.0	m ²	18,500	55,500	
7	ファサード床 モルタル左官仕上	補修材 金コテ押え	2.0	m ²	6,500	13,000	
合 計						304,500	

見 積 御 内 記

名称	塗装工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	天井・壁艶消し塗装	下地処理含む	180.0	m ²	2,400	432,000	
2	建具・窓枠塗装		1.0	式		98,000	
3	カウンター、テーブルワックス仕上		1.0	式		25,000	
4	外部塗装	正面	15.0	m ²	2,000	30,000	
5	雑塗装	黒板塗装など	1.0	式		65,000	
6	床防塵クリア塗装		1.0	式		25,000	
合 計						675,000	

見 積 御 内 記

名称	電気設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	電気配線工事		1.0	式			
2	LEDスポットライト・ダウンライト		8.0	灯	6,500	52,000	
3	動力盤	スチールオーダー	1.0	ヶ所			
4	スイッチ、コンセント改修、器具取付費		1.0	式			
5	裸電球吊り下げ照明		4.0	灯	7,500	30,000	
6	テンポ内部ライティングレール	4m	5.0	本			
7	看板灯	アンティーク	1.0	灯	40,000	40,000	
8	動力引き込み工事	申請費	1.0	式			
9	厨房ベース照明		4.0	台	26,000	104,000	
10	電灯盤	12分岐 予備3	1.0	台			
11	ブラケット照明		2.0	灯	30,000	60,000	
12	アンティークシェイドランプ		2.0	灯	50,000	100,000	
13	外部照明	アーム式スポットライト	2.0	灯	18,500	37,000	
	※電気工事別途						
	※照明器具のみ弊社手配						
合 計						423,000	

見 積 御 内 記

[illegible]

見 積 御 内 記

名称		給喚気・ダクト設備工事					
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	ステンレスフード	1800×1200	1.0	式		100,000	
1	天井換気扇	オール金属タイプ大風量	1.0	ヶ所		55,000	
2	同上ダクト工事		1.0	式		88,000	
3	トイレ換気扇	配管工事含む	1.0	ヶ所		60,000	
合 計						303,000	

見 積 御 内 記

名称		内装工事					
NO	項　目	摘　要	数量	単位	単　価	金　額	備　考〈定　価〉
1	長尺シート貼り(ドライキッチン用)	厨房・トイレ・前室	30.0	m ²	5,500	165,000	
2	ソフト巾木		1.0	式		45,000	
合　　　計						210,000	

見 積 御 内 記

名称	空調設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	空調設備工事	別途	1.0	式			
合 計							

見 積 御 内 記

名称	消防設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	消防設備工事	概算 別途 要打ち合わせ	1.0	式		250,000	
合 計						250,000	

九 復 師 附 臥

見 積 御 内 記

[illegible]

見 積 御 内 記

名称	値引き						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	値引き		1.0	式		-6,800	
合 計						-6,800	

見 積 御 内 訳

[illegible]