

総 合 見 積 書

貴社名
担当者
物件名
ラーメン店 新装工事
お見積総額(税抜き) ¥7,000,000 -
消費税 ¥700,000 -

御受渡条件 検収渡しと致します
御取引条件 ご契約書に基づく
見積記載以外の項目は別途費用が掛かります。
御取引期日 ご契約書に基づく
見積有効期限 提出日より30日間

NO	項 目	摘 要	数量	単位	単 価	金 額	備 考
1	仮設工事		1	式		227,480	
2	土工事		1	式		435,600	
3	左官工事		1	式		559,650	
4	軽鉄工事		1	式		1,282,820	
5	造作、金物、建具工事		1	式		640,000	
6	内装工事		1	式		280,000	
7	塗装工事		1	式		173,000	
8	給排水設備工事		1	式		339,000	
9	設備工事		1	式		565,000	
10	換気ダクト設備費		1	式		1,141,500	
11	電気設備工事		1	式		528,100	
12	衛生設備工事		1	式		244,200	
13	ガス設備工事		1	式		300,000	
14	諸経費		1	式		283,650	
合 計						¥7,000,000	
備 考 ※防災工事は別途と致します。							
※工事費用は日中工事での計上と致します。							

元 価 目 別

名称	仮設工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	墨出し		44.0	m ²	350	15,400	
2	現場養生		44.0	m ²	430	18,920	
3	資材養生		44.0	m ²	430	18,920	
4	内部足場		44.0	m ²	560	24,640	
5	残材処分		44.0	m ²	1,060	46,640	
6	残材収集運搬		44.0	m ²	780	34,320	
7	仮設資材運搬		44.0	m ²	430	18,920	
8	美装		44.0	m ²	1,130	49,720	
合 計					227,480		

見 積 御 内 訳

名称	土工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	U字溝設置		1.0	式		108,000	
2	砕石敷設		1.0	式		84,000	
3	メッシュ筋敷設		1.0	式		5,600	
4	防水シート張り		1.0	式		19,000	
5	グリストラップ嵩上げ		1.0	式		35,000	
6	会所柵設置		1.0	式		44,000	
7	止め型枠		1.0	式		40,000	
8	グレーチング設置		1.0	式		70,000	
9	雑材消耗品		1.0	式		30,000	
合 計						435,600	

見 積 御 内 訳

名称	左官工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	土間コンクリート		2.6	m ²	34,000	88,400	
2	土間打設		1.0	式		78,000	
3	厨房金鋏押え		16.0	m ²	6,300	100,800	
4	厨房土間高さだし		1.0	式		23,000	
5	厨房壁モルタル		22.5	m ²	2,100	47,250	
6	レベラー打設		24.0	m ²	7,800	187,200	
7	雑材消耗品		1.0	式		35,000	
合 計						559,650	

見 積 御 内 訳

名称	軽鉄工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	天井下地		44.0	m ²	3,000	132,000	
2	吊元金具		44.0	m ²	600	26,400	
3	設備開口補強		6.0	ヶ所	8,400	50,400	
4	天井点検口		4.0	台	7,000	28,000	
5	壁下地		99.0	m ²	3,500	346,500	
6	吊り戸棚部壁補強		1.0	式		45,000	
7	天井ボード		44.0	m ²	2,600	114,400	
8	階段下下がり天井		1.0	式		63,000	
9	間仕切り下地		36.0	m ²	2,600	93,600	
10	壁ボード		99.0	m ²	2,000	198,000	
11	カウンター腰壁		8.0	m	7,000	56,000	
12	腰壁ボード		12.2	m ²	2,000	24,400	
13	腰壁ケイカル		12.2	m ²	4,600	56,120	
14	資材運搬		1.0	式		49,000	
合 計						1,282,820	

見 積 御 内 訳

名称	造作、金物、建具工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	カウンターテーブル		1.0	式		123,000	
2	テーブル組立設置		1.0	式		86,000	
3	厨房壁SUSパネル		1.0	式		63,000	
4	入り口ガラス戸		1.0	式		198,000	
5	ガラス戸設置		1.0	式		95,000	
6	ガスメーターボックス造作		1.0	式		75,000	
合 計						640,000	

見 積 御 内 訳

名称	内装工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	クロス	客席天井	24.0	m²	1,250	30,000	
2		客席壁	76.0	m²	1,250	95,000	
3		トイレ 壁・天井	1.0	式		60,000	
4	長尺防水シート	客席床	1.0	式		95,000	
合 計						280,000	

見 積 御 内 訳

名称		塗装工事					
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	塗装仕上げ	厨房壁	22.0	m ²	2,500	55,000	
2		厨房天井	20.0	m ²	3,100	62,000	
3	床防水トップ仕上げ	厨房床	20.0	m ²	2,800	56,000	

見 積 御 内 訳

名称	給排水設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	排水	雑排水配管	1.0	式		123,000	
1		汚水配管	1.0	式		29,000	
2	給水	給水管	1.0	式		86,000	
3		支持金物	1.0	式		9,000	
4	給湯	給湯管	1.0	式		84,000	
5		支持金物	1.0	式		8,000	
合 計						339,000	

見 積 御 内 訳

名称	設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	グリストラップ設置		1.0	台		220,000	
2	器具取付接続		1.0	式		133,000	
3	カラン取付		1.0	式		49,000	
4	給湯器16号		1.0	台		134,000	
5	水圧通水試験		1.0	式		29,000	
合 計						565,000	

見 積 御 内 訳

名称	換気ダクト設備費						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	トイレ換気扇		1.0	ヶ所		41,800	
2	客席換気扇		2.0	ヶ所	44,800	89,600	
3	厨房シロッコファン		1.0	台		200,000	
4	ダクトフード		1.0	台		273,000	
5	ダクト配管		16.0	m	23,000	368,000	
6	支持金物		1.0	式		40,000	
7	ベントキャップ		4.0	台	7,300	29,200	
8	給気配管		1.0	式		54,000	
9	防火ダンパー		1.0	台		31,300	
10	給気口		2.0	ヶ所	7,300	14,600	
合 計						1,141,500	

見 積 御 内 訳

名称	電気設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	照明配線		5.0	回路	6,800	34,000	
3	渡り配線		30.0	ヶ所	4,800	144,000	
4	スイッチ配線		5.0	ヶ所	9,800	49,000	
5	電話用弱電空配管		1.0	ヶ所		7,000	
6	コンセント		14.0	ヶ所	16,300	228,200	
7	看板用電源配線		1.0	ヶ所		16,900	
8	換気扇電源		1.0	式		49,000	
合 計						528,100	

見 積 御 内 訳

名称	衛生設備工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	便器		1.0	式		46,600	
2	ウォシュレット		1.0	式		73,000	
3	棚付き2連紙巻器		1.0	式		3,200	
4	台付自動水栓		1.0	式		65,900	
5	床排水金具		1.0	式		15,000	
6	器具送料		1.0	式		32,500	
7	器具設置		1.0	式		8,000	
合 計						244,200	

見積御内訳

名称		ガス設備工事					
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	ガス配管		1.0	式		300,000	
合 計						300,000	

見 積 御 内 訳

名称	諸経費						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	現場管理費		1.0	式		350,000	
2	現場諸経費		1.0	式		200,000	
3	会社経費		1.0	式		150,000	
4	値引き		1.0	式		-416,350	
合 計						283,650	