見積書

御中 見積 No.

件名: 秋葉原オフィス 改装計画①

現場住所:

下記のとおり、お見積り致します。

納期: 別途ご相談 支払条件: 契約書による

見積有効期限: 見積後30日

合計金額 ¥2,090,000 (稅込)



No.	摘要	数量	単価	金額
	秋葉原オフィス 改装計画①	1 式		1,939,684
	明細は別紙のとおりとします。			
	出精値引	1 式		-39,684
	面談フロア 6ブースなど			
_				
_				
		小計		¥1,900,000
		消費税		¥190,000
		合計		¥2,090,000

|--|

No.	名 称	適	用	数量	単 位	単 価	金 額	備	考
1	仮設工事			1.00	式		140,000		
2	解体工事			1.00	式		454,000		
3	造作工事			1.00	式		550,400		
4	内装仕上工事			1.00	式		333,200		
5	電気工事			1.00	式		166,200		
6	諸経費			1.00	式		295,884		
	※家具什器工事は別途								
		1							
		1							
		1							
	合計						1,939,684		

No.	名	称	適	用	数量	単 位	単 価	金 額	備	考
	仮設工事									
	養生費				1.00	式	50,000	50,000		
	仮設材				1.00	式	20,000	20,000		
	発生残材処分費	•			1.00	式	20,000	20,000		
	引き渡し清掃費				1.00	式	50,000	50,000		
	合計							140,000		

No.	名 称	適	用	数量	単 位	単 価	金 額	備 考
	解体工事							
	養生費			1.00	式	30,000	30,000	
	既存引戸撤去			1.00		20,000	20,000	
	既存開戸撤去			1.00	式	15,000	15,000	
	腰壁撤去			2.00	m [*]	2,000	4,000	
	間仕切壁解体			25.00	m [*]	2,000	50,000	10㎡増
	壁面クロス撤去			45.00	m [*]	1,000	45,000	5 ㎡ 増
	トイレクロス部分撤去			10.00	m [*]	1,000	10,000	
	雑解体費			1.00	式	20,000	20,000	
	解体材搬出費			1.00	式	70,000	70,000	
	運搬費			1.00	式	70,000	70,000	
	解体処分費			1.00	式	120,000	120,000	
	※既存オフィス機器の移設作	F業等は別途とす	⁻ る					
	合計						454,000	

No.	名 称	適	用 数量	単 位	単 価	金額	備 考
	造作工事						
	新設ふさぎ壁 H2440	LGS65	3.00	m [*]	2,800	8,400	
		PB12.5	6.00		2,000	12,000	
	新設腰壁 H1700	LGS65	32.00	m [*]	3,500	112,000	
		PB12.5	64.00		2,000	128,000	
	開口補強		10.00	m	8,500	85,000	
	副資材		1.00	恜	30,000	30,000	
	資材揚重費		1.00	式	50,000	50,000	
	運搬諸経費		1.00	式	40,000	40,000	
	笠木	98×11	20.00	m	2,500	50,000	材料変更で減
	開口塞ぎパネル	H600	7.00	m			無
	上部用 見切金物		20.00	m			無
	上記 下地		1.00	式			無
	上記 取付施工費		1.00	式	35,000	35,000	
	新設建具		1.00	枚			既存転用
	合計					550,400	

No.	名 称		適	用	数量	単 位	単 価	金 額	備	考
	内装仕上工事									
	タイルカーペット部分ろ	を換 500×50	00		15.00	枚	520	7,800	想定	
	ソフト巾木				1.00	式	10,000	10,000		
	副資材				1.00		10,000	10,000		
	施工費				1.00		35,000	35,000		
	新設壁クロス貼	材工			70.00		2,200	154,000		
	トイレクロス	材工			12.00	m [*]	2,200	26,400		
	天井塗装補修	ジプトン			1.00	式	40,000	40,000		
	養生費				1.00	式	20,000	20,000		
	運搬搬入費				1.00	式	30,000	30,000		
	合計							333,200		

No.	名	称	適	用	数量	単 位	単 価	金 額	備	考
	電気工事									
	配線材				1.00	式	10,000	10,000		
	ハーネスケーブル				6.00	個	7,200	43,200		
	LANケーブル				40.00	m	200	8,000		
	上記 施工費				1.00	式	70,000	70,000		
	消耗品雑材				1.00	式	20,000	20,000		
	運搬搬入費				1.00	式	15,000	15,000		

No.	名 称	適	用	数量	単 位	単 価	金 額	備	考
	諸経費								
	現場管理費			1.00	式	82,190	82,190		
	現場経費			1.00		82,190	82,190		
	会社経費			1.00		131,504	131,504		
	合計						295,884		