

総 合 見 積 書

貴社名                      御中

担当者                      様

物件名                      オフィス移転工事

お見積総額(税抜き)                      ¥2,100,000 -

消費税                      ¥210,000 -


御受渡条件                      検収渡しと致します

御取引条件                      ご契約書に基づく

見積記載以外の項目は別途費用が掛かります。

御取引期日                      ご契約書に基づく

見積有効期限                      提出日より30日間



NO	項 目	摘 要	数量	単位	単 価	金 額	備 考
1	パーティション工事		1	式		1,441,000	
2	表装工事		1	式		466,500	
3	サイン工事		1	式		68,000	
4	美装工事		1	式		50,000	
5	諸経費		1	式		100,000	
6	御値引き		1	式		-25,500	
7							
8							
9							
10							
11							
12							
13							
14							
合 計						¥2,100,000	
備 考							

# 見 積 条 件 書

[illegible]

## 見積御内訳

名称		パーティション工事					
NO	項　目	摘　要	数量	単位	単　価	金　額	備　考〈定　価〉
	スチール間仕切(MW-70)						
	■表面材：焼付塗装鋼板(当社標準色) ■芯材：石膏ボード						
1	会議室	W11546.5×H2388×D70	1.0	ヶ所			
2	製品代		1.0	式		619,400	〈 1,238,800 〉
3	施工費		1.0	式		130,000	
4	ガラス工事		1.0	式		621,600	〈 1,243,200 〉
5	運搬搬入費		1.0	式		70,000	
合　　　計						1,441,000	

## 見積御内訳

名称	表装工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
	※規定㎡数以下に付(資材施工費分け)						
1	既存タイルカーペット剥ぎ手間下地処理		35.0	㎡	500	17,500	
2	東リ・GX3701		6.0	ケース	35,000	210,000	
3	東リ・TTN3122		9.0	ケース	20,000	180,000	
4	ピールアップ糊(小)		1.0	個		9,000	
5	施工費		1.0	式		50,000	
合 計						466,500	



## 見積御内訳

名称	サイン工事						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	亚克力5t切り文字	W850・950 出力+木口塗装	1.0	式		40,000	
2	現場施工費		1.0	式		28,000	
合 計						68,000	



## 見 積 御 内 記

[illegible]

## 見 積 御 内 記

名称	諸経費						
NO	項 目	摘 要	数量	単位	単 価	金 額	備 考〈定 価〉
1	諸経費		1.0	式		100,000	

